

जानकी देवी मेमोरियल कॉलेज
(दिल्ली विश्वविद्यालय)

JANKI DEVI MEMORIAL COLLEGE
(University Of Delhi)

सर गंगा राम अस्पताल मार्ग, नई दिल्ली-११००६०
Sir Ganga Ram Hospital Marg, New Delhi-110060

दूरभाष : २५७८७७५४ फैक्स : २५७९०८३२

Tel. : 25787754, Fax : 25710832

E-mail : jdmcollege@hotmail.com, http://jdm.du.ac.in



संदर्भ संख्या/Ref. No. 41.2

Notice Inviting Quotations

दिनांक/Dated. 02-07-2019

Sealed Item rate quotations are invited for works mentioned below from contractors who had executed similar works in PWD/DDA/MCD/NDMC/ Delhi University/any institutions. Quotations supported by GST registration no. PAN, TAN, experience certificate, and other relevant documents shall be submitted on letter head of the firm/Company along with the proof of execution of similar works during last 3 years. Contractors/Vendors may visit to the College to see the work/site on any working day from 03:00 pm. Last date of submission of quotation is 10-07-2019 up to 03:00 pm which shall be opened on same date at 03:30pm in the office of Principal Janki Devi Memorial College (JDMC). Quotation received after the last date for whatsoever reason will not be considered. In case of any dispute (S) the decision of the undersigned will be final and binding. The Undersigned reserves the right to reject all the quotations or any one full or in part without assigning any reason thereof.

Name of Work- Quotation/Estimate for Retrofitting at JDMC.

Scopes of work are as follows:-

Estimate for Retrofitting Work					
S.no	Description	Qty	Unit	Rate	Amount
1	Chipping of existing cement plaster manually from masonry or concrete surface using chisel and hammer disposal of debris within a lead of 50m complete.	65	Sqm		
2	Cleaning reinforcement of total rust by tapping & using mechanical wire brush or any other suitable way including from behind and around the reinforcement bars to give it that ally rust free finished steel surface. Rebellng primer SB-R equivalent (mode of measurement-concrete surface area with exposed Reinforcement).	55	Sqm		
3	Providing & application of bond coat on the concrete surface by mixing high dispersion SBR latex like Master Emco SBR 2 of BASF with white cement in the ratio of 2:3, The mixing should be done to a lump free consistency for the bond coat and the screed/ mortar should be applied once the bond coat is tacky. Master Emco SBR 2 of BASF or Nittobond SBR 2 (Latex) of Forsook or Equivalent.as per-direction of engineer-in-charge.	65	Sqm		



4	Providing & supplying the one component, Polymer modified cementations anti-corrosive primer (having the technical parameters mentioned in material specifications) formulated to provide dual protection of a polymeric barrier and an integral corrosion - inhibiting system , to the existing steel & additional steel provided before patching of damaged areas, using suitable tools and equipment inclusive of Material, Manpower and	50	Sqm		
	Equipment. BASF Master Emaco P 130/Fosroc Nonprime Zincrich / Sika Rust off 100 or other equivalent (mode of measurement - concrete surface area with exposed reinforcement).as per direction of Engineer-in-charge.				
5	Providing, making fixing & anchoring of reinforcing bars or dowels or rebar including drilling the holes, fixing the bar and grout the bar with Hilty HIT -HY-150 grouting chemical, all labour all tools & plants, necessary scaffolding etc but excluding the reinforcement steel complete for all lead & lift as per direction by Engineer Incharge /structural consultants or Architect. Rebaring depth minimum 300 mm or 20 D whichever is more. Note:-8mm dia to 10 mm dia of steel.	30	Eatch		
6	12mm cement plaster of mix (Junction of all RCC and brick shall be provided with chicken wire mesh of 150mm width on either side of the junction before plastering)				
6.1	1:3:3 (1cement:3course sand :3fine sand)	60	Sqm		
7	Providing and using single component cement based non-shrink micro concrete of approved manufacture by mixing graded stone aggregate 10mm and down and coarse sand as per manufactures specification & direction of Engineer-in-charge complete as per design and approved by Engineer-in-charge at all floor and all Heights. Note:-25mm to 35mm depth.	40	Sqm		
8	Providing and fixing double scaffolding system (cup lock type) on the exterior side up to seven store height made with 40mm dia m.s tube 1.5m center to center horizontal & vertical tube joining with cup & lock system with m.s tube, m.s tube challies, m.s clamps and m.s stair case system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter. The scaffolding system shall be stiffened with bracing ,runner connection with the building etc. wherever required for inspection of work at required locations with essential safety features for the as per Direction of engineer-in-charge.	80	Sqm		
			Total Amount		

NOTE: - APPLICABLE G.S.T 18% EXTRA.





जानकी देवी मेमोरियल कॉलेज
(दिल्ली विश्वविद्यालय)

JANKI DEVI MEMORIAL COLLEGE
(University Of Delhi)

सर गंगा राम अस्पताल मार्ग, नई दिल्ली-११००६०
Sir Ganga Ram Hospital Marg, New Delhi-110060
दूरभाष : २५७८७७५४ फ़ैक्स : २५७९०८३२
Tel. : 25787754, Fax : 25710832
E-mail : jdmcollege@hotmail.com, http://jdm.du.ac.in

संदर्भ संख्या/Ref. No. 412

दिनांक/Dated 02-07-2019

Terms & Conditions

1. Work shall be done as per latest CPWD specification 2014 with up to date Corrections Slips and direction of Engineer/Architect/Site in – charge.
2. Water and electricity shall be supplied by College and recovery @ 1 % for water and 1 % for electricity shall be made from dues of contractor.
3. 10 % of the cost shall be retained as security deposit and shall be released after one year of defect liability period.
4. Time allowed to complete the work is 30 days from date of issue of work order. Work is to be completed within 30 days from date of start of work otherwise compensation @ 1 % (One per cent) of Cost of work per day subject to maximum of 10% of cost of work shall be recovered from contractor's bill.
5. TDS for Income Tax & labor cess shall be deducted as per govt. rules from dues/bill of the contractor.
6. Rates shall be inclusive of all Taxes including GST, Octrio, Cartages, loading, unloading etc. nothing extra is payable.
7. Rate quoted shall be including of GST, as applicable. Any changes/revision of Rate in Taxes made by Govt. after award of work shall be adjusted upward or downward, as the case may be.
8. Sample of all Material/Item/Equipment shall be got approved before use by engineer/architect/competent authority.
9. Decision of Principal JDMC shall be final and binding in case of any dispute or interpretation of Description of item in B.O.Q/Specification of work or any other criterion. College is not bound to give work to L1.
10. Site shall be handed over in neat and clean condition after removing all Malba/Surplus Material/Site Stores/Jhuggi/Hutments etc.



Swati Pal
Dr. Swati Pal
Principal
[Signature]