



जानकी देवी मेमोरियल कॉलेज
(दिल्ली विश्वविद्यालय)
JANKI DEVI MEMORIAL COLLEGE
(University Of Delhi)
सर गंगा राम अस्पताल मार्ग, नई दिल्ली-११००६०
Sir Ganga Ram Hospital Marg, New Delhi-110060
दूरभाष : २५७८७७५४ फैक्स : २५७९०८३२
Tel. : 25787754, Fax : 25710832
E-mail : jdmcollege@hotmail.com, http://jdm.du.ac.in

संदर्भ संख्या/Ref. No. 1289.....

दिनांक/Dated...12-03-2020.....

Notice Inviting Quotations

Sealed Item rate quotations are invited for works mentioned below from contractors who had executed similar works in PWD/DDA/MCD/NDMC/ Delhi University/any institutions. Quotations supported by GST registration no. PAN, TAN, and other relevant documents shall be submitted on letter head of the firm/Company for execution of similar works during last 3 years. Contractors/Vendors may visit to the College to see the work/site on any working day from 10:00 am to 05:00 pm. Last date of submission of quotation is 19-03-2020 up to 03:00 pm which shall be opened on same date at 03:30pm in the office of Principal Janki Devi Memorial College (JDMC). Quotation received after the last date for whatsoever reason will not be considered. In case of any dispute (S) the decision of the undersigned will be final and binding. The Undersigned reserves the right to reject all the quotations or any one full or in part without assigning any reason thereof.

Name of work:- Providing and Fixing Kerb Stones along the Ground in front of Staff Flats at Janki Devi Memorial College New Delhi-110060

S.No	Description	Qty.	Rate in Rs.	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	10.00		
2	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	5.00		

3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	40.00		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	2.00		
			Total	

Terms & Conditions

1. Providing and Fixing Kerb Stones along the Ground in front of Staff Flats at JDMC New Delhi to be done as per latest CPWD specification 2016 with up to date Corrections Slips and direction of Engineer/Architect/Site in – charge.
2. Water and electricity shall be supplied by College and recovery @ 1 % for water and 1 % for electricity shall be made from dues of contractor.
3. 10 % of the cost shall be retained as security deposit and shall be released after one year of defect liability period.
4. Time allowed to complete the work is 30 days from date of issue of work order. Work is to be completed within 30 days from date of start of work otherwise compensation @ 1 % (One per cent) of Cost of work per day subject to maximum of 10% of cost of work shall be recovered from contractor's bill.
5. TDS for Income Tax & labor cess shall be deducted as per govt. rules from dues/bill of the contractor.
6. **Rates shall be inclusive of all Taxes including GST, Octrio, Cartages, loading, unloading etc. Nothing extra is payable.**
7. Sample of all Material/Item/Equipment shall be got approved before use by engineer/architect/competent authority.
8. Decision of Principal JDMC shall be final and binding in case of any dispute or interpretation of Description of item in B.O.Q/Specification of work or any other criterion.
9. Site shall be handed over in neat and clean condition after removing all Malba/Surplus Material/Site Stores/Jhuggi/Hutments etc.

Swati Pal

Dr. Swati Pal

Principal

Dr. Swati Pal