



जानकी देवी मेमोरियल कॉलेज
(दिल्ली विश्वविद्यालय)
JANKI DEVI MEMORIAL COLLEGE
(University Of Delhi)

सर गंगा राम अस्पताल मार्ग, नई दिल्ली-११००६०
Sir Ganga Ram Hospital Marg, New Delhi-110060
दूरभाष : २५७८७७५४ फ़ैक्स : २५७९०८३२
Tel. : 25787754, Fax : 25710832
E-mail : jdmcollege@hotmail.com, http://jdm.du.ac.in

संदर्भ संख्या/Ref. No. 759

दिनांक/Dated 02/03/21

Notice Inviting Quotations (NIQ)

Sealed item rate quotations are invited for works mentioned below from contractors who had executed similar works in PWD/DDA/MCD/NDMC Delhi University/ any institutions. Quotations supported by GST registration no., PAN, experience certificate, EMD of Rs. 5000/- in favour of Principal JDMC in the form of DD payable at Delhi and other relevant documents if any shall be submitted on the letter head of the firm/Company/Vendor etc along with the proof of execution of similar works during last 3 years. Contractors /Vendors may visit to the College to see the work/site on any working day from 09:00am to 05:00pm. Last date of submission of quotation is 16-03-2021 up to 03:00 pm which shall be opened on same date at 03:30pm in the office of Principal Janki Devi Memorial College (JDMC). Quotation received after the last date for whatsoever reason will not be considered. In case of any dispute (S) the decision of the undersigned will be final and binding. The Undersigned reserves the right to reject all the quotations or any one full or in part without assigning any reason thereof.



Scopes of Work- Providing & Fixing Floor Tiles, False Ceiling, Painting work etc complete of Girls Common Room (GCR) at JDMC.

BOQ floor tiles, False Ceiling painting work of girls common room at jdmc.						
Sr.no.	Description of item	Unit	Qty.	Rate	Amount	
1.00	Providing and fixing 1st quality vitrified floor tiles (600x600) conforming to IS:15622 (thickness to be specified by the manufacture), of approved make, in all colours, shades except any size as approved by engineer-in-charge, in skirting etc. 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointing with white cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete as per direction of engineer-in-charge. (note: Approved brand Kajaria, Somany, NITCO)	Sqm	58.00			
2.00	Disposal of excess earth/building rubbish/ malba /similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by engineer-in-charge, beyond 50m initial lead, for all lead including all lifts involved.	Trip	3.00			
3.00	dismantling tiles work in floor and roofs laid in cement mortar including staking material within 50mtr lead.	Sqm	58.00			
4.00	Providing and applying white cement base putty of average thickness 1mm of approved brand and manufacture over the plastered	Sqm	210.00			



	wall surface to prepare the surface even and smooth complete.					
5.00	Removing dry oil bound distemper,water proofing cement paint and the like by scrapping sand papering the prepring the surface smooth including necessary repaire to scratches etc. complete as per direction of engineer-in-charge.	Sqm	210.00			
6.00	Painting with wether coat,water proofing,Apex Paint of approved brand manufacturing of required any colour to given and even shade:					
6.a	Two or more coats on old work.	Sqm	300.00			
7.00	Providing and fixing false ceiling at all height with Ceiling Tile of Armstrong Make Dune max RH99 or equivalent from Gyproc Only 595x595 mm of approved texture, design and pattern having moisture content less than 2 % humidy resistance of 99% as per IS 8225:1987, non-combustibleas per BS 476-1970 and galvanized @ 120gram per sqm including both side comprising of main T- runners of size 15x32 mm of length 3000mm, cross-T of size 15x32 mm of length 1200mm etc. the work shall be carried out as per specifications, drawing and as per direction of engineer-in charge .	Sqm	60.00			
	Tax: Applicable G.S.T 18% EXTRA.			TOTAL AMOUNT		

Terms & Conditions for work of Providing & Fixing Floor Tiles, False Ceiling, Painting Work etc complete of Girls Common Room (GCR) at JDMC

1. Work shall be done as per latest CPWD specification 2018 with up to date Corrections Slips and direction of Engineer/Architect/Site in – charge etc.
2. Water and electricity shall be supplied by the College and recovery @ 1 % for water and 1 % for electricity shall be made from dues of Contractor/Vendors. 10% of cost of work shall be retained as security deposit for defect liability period for one year from date of actual completion of work.



3. Time allowed to complete the work is 30 days from date of issue of work order. Work is to be completed within 30 days from date of start of work otherwise compensation @ 1 % (One per cent) of Cost of work per day subject to maximum of 10% of cost of work shall be recovered from contractor's bill.
4. TDS for Income Tax & labour cess shall be deducted as per govt. rules from dues/bill of the contractor.
5. Rate quoted shall be inclusive of all Taxes including GST, Octrio, Cartages, loading, unloading etc. Nothing extra is payable. Any changes/revision of Rate in Taxes made by Govt. after award of work shall be adjusted upward or downward, as the case may be.
6. Sample of all Material/Item/Equipment etc shall be got approved before use by engineer/architect/competent authority etc.
7. Decision of Principal JDMC shall be final and binding in case of any dispute or interpretation of Description of item in B.O.Q/Specification of work/any other criterion. College is not bound to give work to L1 Full or in part without assigning any reason thereof.
8. Site shall be handed over in neat and clean condition in writing after removing all Malba/Surplus Material/Site Stores/Jhuggi/Hutments etc.



Swati Pal

Prof. Swati Pal

Principal

[Signature]