



जानकी देवी मेमोरियल कॉलेज
(दिल्ली विश्वविद्यालय)
JANKI DEVI MEMORIAL COLLEGE

(University Of Delhi)

सर गंगा राम अस्पताल मार्ग, नई दिल्ली-११००६०
Sir Ganga Ram Hospital Marg, New Delhi-110060

दूरभाष : २५७८७७५४ फैक्स : २५७९०८३२

Tel. : 25787754, Fax : 25710832

E-mail : jdmcollege@hotmail.com, http://jdm.du.ac.in

संदर्भ संख्या/Ref. No. 225

दिनांक/Dated 9/9/2020

Notice Inviting Quotations

Sealed Item rate quotations are invited for works mentioned below from contractors who had executed similar works in PWD/DDA/MCD/NDMC/ Delhi University/any institutions. Quotations supported by GST registration no. PAN, TAN, experience certificate, and other relevant documents shall be submitted on letter head of the firm/Company along with the proof of execution of similar works during last 3 years. Contractors/Vendors may visit to the College to see the work/site on any working day from 09:00 am to 05:00 pm. Last date of submission of quotation is 16-09-2020 up to 03:00 pm which shall be opened on same date at 03:30pm in the office of Principal Janki Devi Memorial College (JDMC). Quotation received after the last date for whatsoever reason will not be considered. In case of any dispute (S) the decision of the undersigned will be final and binding. The Undersigned reserves the right to reject all the quotations or any one full or in part without assigning any reason thereof.

Scopes of work renovation work of Gents Toilet at JDMC

Sr.no.	Description of item	Unit	Qty	Rate	Amount
1	Demolishing dry bricks pitching in floors,sunkers toilet,drains etc.including of serviceable material and disposal of unserviceable material with in 50 mtr lead.	cum	5		
2	Dismantling of flushing cistern of all types (CI,PVC,Vitrious china) including staking of useful materials near the site and disposal of materials with in 50mtr lead.	Each	2		
3	Providing and fixing water closet squatting pan (indian types W.C pan) with 100mm send cast iron P or S trap ,10liter low level white pvc flushing cistern,including flush pipe with manually controlled device (handle lever)conforming to IS:7231, with all fittings and fixtures complete,including cutting and making good the	Each	1		
4	Providing and fixing white vitreous china pedestal water closet (European types W.C pan) with set and lid,10liter low level white pvc flushing cistern,including flush pipe with manually controlled device (handle lever)conforming to IS:7231, with all fittings and fixtures complete,including cutting and making good the floors,wall wherever required: w.c pan with isi marked white solid plastic seat and lid.	Each	1		
5	Disposal of excess earth/building rubbish/ malba /similar unservice able ,dismantled or wate materials by mechanical means including loading ,transporting ,unloading to approved municipal dumping ground or as approved by engineer-in-charge, beyound 50m initial	Trip	2		



6	Providing and applying tapecrete (minium2 coats) water proofing to sunken toilet,balcony,chajja as per manufacture's specification including base plaster & protective cement plater in horizontal and vertical surface- surface to be punned with neat cement complete.	sqm	15		
7	Providing and fixing 1st quality vitrified wall tiles ,floor tiles (200x300),(300x300) conforming to IS:15622 (thickness to be specified by the manufacture),of approved make ,inn all colours, shades except any size as appoved by engineer-in-charge,in skirting etc. 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse send) and jonting with white cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete as per direction of engineer-in-charge.	sqm	15		
8	providing and fixing pvc water pipe. (Astral,supream,price etc)				
8.a	100 mm dia	mtr.	2		
9	Providing and fixing 100mm PVC for SWR gully trap.(Astral,supream,prince etc.)				
9.a	100mm dia	each	2		
10	Filling available bricks pitching in trenches,plinth sides of foundations, floor,sunken area,toilet etc. in layers not exceeding 20cm in depth ,consolidating each deposited layer by ramming and watering ,lead up to 50 m and liftup to 1.5m.	cum	4.5		
Total Amount including GST					



Terms & Conditions for work renovation work of gents toilet at JDMC

1. Work shall be done as per latest CPWD specification 2018 with up to date Corrections Slips and direction of Engineer/Architect/Site in – charge.
2. Water and electricity shall be supplied by the College and recovery @ 1 % for water and 1 % for electricity shall be made from dues of Contractor/Vendors.
3. 10 % of the cost shall be retained as security deposit and shall be released after one year of defect liability period.
4. Time allowed to complete the work is 30 days from date of issue of work order. Work is to be completed within 30 days from date of start of work otherwise compensation @ 1 % (One per cent) of Cost of work per day subject to maximum of 10% of cost of work shall be recovered from contractor's bill.
5. TDS for Income Tax & labor cess shall be deducted as per govt. rules from dues/bill of the contractor.
6. Rates shall be inclusive of all Taxes including GST, Octrio, Cartages, loading, unloading etc. nothing extra is payable.
7. Rate quoted shall be including of GST, as applicable. Any changes/revision of Rate in Taxes made by Govt. after award of work shall be adjusted upward or downward, as the case may be.
8. Sample of all Material/Item/Equipment shall be got approved before use by engineer/architect/competent authority.
9. Decision of Principal JDMC shall be final and binding in case of any dispute or interpretation of Description of item in B.O.Q/Specification of work or any other criterion. College is not bound to give work to L1.
10. Site shall be handed over in neat and clean condition in writing after removing all Malba/Surplus Material/Site Stores/Jhuggi/Hutments etc.



Dr. Swati Pal

Dr. Swati Pal

Principal