



जानकी देवी मेमोरियल कॉलेज
(दिल्ली विश्वविद्यालय)

JANKI DEVI MEMORIAL COLLEGE
(University Of Delhi)

सर गंगा राम अस्पताल मार्ग, नई दिल्ली-११००६०
Sir Ganga Ram Hospital Marg, New Delhi-110060

दूरभाष : २५७८७७५४ फैक्स : २५७९०८३२

Tel. : 25787754, Fax : 25710832

E-mail : jdmcollege@hotmail.com, http://jdm.du.ac.in

संदर्भ संख्या/Ref. No. 50

दिनांक/Dated 13/05/2021

Notice Inviting Quotations

Sealed Item rate quotations are invited for the works mentioned below from the Contractors/Vendors/Firm/Company etc., who has executed the similar works in PWD/DDA/MCD/NDMC/Delhi University/any institutions etc. Quotations supported by GST registration no. PAN, TAN, experience certificate, EMD of Rs. 5000/- in favor of the Principal JDMC in the form of DD payable at Delhi and other relevant documents if any shall be submitted on the letter head of the Contractors/Vendors/Firm/Company etc. along with the proof of execution of the similar works during last 3 years. Contractors/Vendors/Firm/Company etc. may visit to the College to see the work/site on any working day from 09:00 am to 05:00 pm. Last date for submission of the quotation is 28th May, 2021 up to 03:00 pm which shall be opened on the same date at 03:30 pm in the office of the Principal Janki Devi Memorial College (JDMC). Quotations received after the last date for whatsoever reason will not be considered. In case of any dispute (s) the decision of the undersigned will be final and binding and subject to jurisdiction of Delhi only. The Undersigned reserves the right to reject all the quotations or any one full or in part without assigning any reason thereof.

SCOPE OF WORK: - Re-construction work of the Chajja in Library at JDMC.

Sr.no.	Description of item	Unit	Qty.	Rate	Amount	Remarks
1	Demolishing R.C.C work in columns, Beam, Slabs, staircase waist slab etc. including all covering plaster/flooring etc. manually by mechanical means including staking of steel bar and disposal of unserviceable material within 50mtr lead as per direction of Engineer-in-charge.	cum	8.00			
2	12mm cement plaster of mix:					
2.a	1:1:2 (1cement:1 coarse sand :2fine sand)	Sqm	100.00			
3	Providing & application of bond coat on the concrete surface by mixing high dispersion SBR latex like Master Emco SBR 2 of BASF with white cement in the ratio of 2:3, The mixing should be done to a lump free consistency for the bond coat and the screed/ mortar should be applied once the bond coat is tacky. Master Emco SBR 2 of BASF or Nittobond SBR-2 (Latex) of Fosroc or Equivalent.	Sqm	10.00			



3a	Disposal of excess earth/building rubbish/ malba /similar un-serviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by engineer-in-charge, beyond 50m initial lead, for all lead including all lifts involved.	Trip	3.00			
4	Providing, making fixing &anchoring of reinforcing bars or dowels or rebar including drilling the holes, fixing the bar and grout the bar with Hilty HIT -HY-150 grouting chemical, all labour all tools & plants, necessary scaffolding etc. but excluding the reinforcement steel complete for all lead & lift as directed by Engineer In-charge /structural consultants or Architect. Re-barring depth minimum 300 mm or 20 D whichever is more.					
4.a	10mm dia	Nos.	40.00			
5	Steel reinforcement of R.C.C work including straightening, cutting banding placing in position and binding all complete up to all level.					
5.a	Thermo-Mechanically Treated bar.	kg	900.00			
6	Providing and laying in position machine batched and machine mixed design mix m25 grade cement concrete for reinforced cement concrete work ,using cement content as per approved design mix. Including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including add mixtures in recommended proportion as per IS:9103 to accelerate retard setting of concrete ,improve workability without impairing strength and durability as per direction of Engineer-in charge.					
6.a	All work above plinth level up to floor VI level.	cum	8.50			
7	Centering and shuttering including strutting, propping etc. and removal of from for all works at all level:					
7.a	Lintels, beams, plinth beam, girders, bressumers and cantilevers.	sqm	60.00			
8	Providing and fixing double scaffolding system (cup lock type)on the exterior side up to seven store height made with 40mm dia. MS tube 1.5m center to center horizontal &vertical tube joining with cup &lock system with MS tube ,MS tube challies, MS clamps and MS stair case system in the scaffolding for working platform etc. .and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter. The scaffolding system shall be stiffened with bracing, runners connection with the building etc. wherever required for inspection of work at required locations with essential safety features for the.	sqm	140.00			
TOTAL AMOUNT (including G.S.T 18%)						



Terms & Conditions for the Work of Reconstruction of Library Chajja at JDMC

1. Work shall be done as per latest CPWD specifications 2018 with up to date corrections, slips and direction of Engineer/Architect/AO/Site-in-charge/caretaker etc.
2. Water and electricity shall be supplied by the College and recovery @ 1 % for water and 1 % for electricity shall be made from dues of Contractors/Vendors/Firm/Company etc. 10% of cost of work shall be retained as security deposit for the defect liability period (DLP) for one year from the date of actual completion of the work.
3. Time allowed to complete the work is one month from date of issue of work order otherwise compensation @1 % (One per cent) of Cost of work per day subject to maximum of 10% of cost of the work shall be recovered from dues/bills of the Contractors/Vendors/ Firm/Company etc.
4. TDS for Income Tax & labor cess shall be deducted as per govt. rules from dues/bills of the Contractors/Vendors/Firm/Company etc.
5. Rate quoted shall be inclusive of all Taxes including of GST, Octroi, Cartages, loading, unloading etc. Nothing extra is payable. Any changes/revision of Rate in Taxes made by Govt. after award of work shall be adjusted upward or downward, as the case may be.
6. Sample of all Material/Item/Equipment etc. shall be got approved by the Engineer/Architect/Competent Authority etc. before use.
7. Decision of the Principal JDMC shall be final and binding in case of any dispute or interpretation in the Description of item in B.O.Q/Specification of work/any other criterion. College is not bound to give work to L1 full or in part without assigning any reason thereof.
8. Site shall be handed over in neat and clean condition in writing after removing of all Malba/Surplus Material/Site Stores/Jhuggi/Hutments etc.



Swati Pal
(PROF. SWATI PAL)
PRINCIPAL
Sw